



Application Ref. No. 4/1743/90

Cliff Walsingham & Co 242 Farnborough Road Farnborough Hants GU14 7JW

DEVELOPMENT ADDRESS AND DESCRIPTION

Marchmont Arms, Piccocts End, Hemel Hempstead,

SUBMISSION OF DETAILS OF LANDSCAPING PURSUANT TO P/P 4/1059/90 (S/S & 2 STOREY EXTNS.INTN & EXTN ALTS)

Your application for the approval of details or reserved matters dated 13.12.1990 and received on 17.12.1990 has been GRANTED, subject to any conditions set out on the attached sheet(s).

Director of Planning.

Date of Decision: 11.02.1991

(encs. - Conditions and Notes).

CONDITIONS APPLICABLE TO APPLICATION: 4/1743/90

Date of Decision: 11.02.1991

DACORUM

Accept details of landscaping.

SCHEDULE OF TREE SURGERY

This schedule to be read in conjunction with Drawing No 220/17.

ref	DESCRIPTION OF WORKS
la - 1B	Boundary zone, existing planting to be retained. Surgery/clearance as follows: Trees to be lightly nruned/shaped, removing dead wood. Shrubs pruned to re-shape within the area. All deadwood, brash, rubbish etc to be cleared from beneath along entire length (to permit cultivation and re-planting by others).
2	Fruit tree group, minor pruning.
3	Birch, prune to re-shape.
4	Yew circle, clip to reinstate formal shape all round, both sides and height (to be agreed). Al/4? existing 'arches' retained. A3/A4 new 'arches' to be cut to match.
5	Birch, prune to re-shape.
6	No work required
7	- do -
8	Yew. Deadwood, clear lower trunk and old stubs, reduce longer limbs to re-shape canopy.
9	Hawthorn - prune to re-shape.
10	Holly - remove.
11	Yew - Deadwood, clear lower trunk and old stubs, reduce longer limbs to re-shape canopy.
12	(Minor surgery to remove any limbs likely to be affected by
13	(building works.

Sub Total carried forward

SHEET

\$.

SCHEDULE OF TREE SURGERY - CONTINUATION :EF DESCRIPTION OF WORKS Holly, minor re-shaping, raise crown to agreed height. 14 15 Chestnuts. Entire group to be felled and removed from site. 15a Stumps to be ground-out to min 300mm below existing soil level. NOTE: All arisings to be removed from site. Supply and install min 1.5m high temporary protective fencing along lines indicated on drawing. Fencing to comprise chestnut pale, taut, and secured to 100 dia poles firmly driven in at 1.5m ø The price for this item should include for removal to allow subsequent landscape works to be carried out (timing to be agreed). Total works Signed On Behalf of

7976

•

Date